## TUMKUR DIVISION.

*Notice dated 14th February* 1930.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 3rd of March 1930, for repairs to Rambhanabantha Channel in Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory notes as earnest money and be superscribed "Tender for repairs to Rambhanabantha Channel in Kunigal Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of his tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office on the evening of the 3rd. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tender.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. The decision of all disputes about rates, measurements, quality of work, etc., and in all matters of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract of estimate of approximate quantities for repairs to Rambhanbantha Channel in Kunigal Taluk.

| No | Details | Unit | Quantity |
|---|---|---|---|
| | I. *Removing silt in Channel.* | | |
| 1 | Earthwork clearing silt including clearing weeds in bed and jungle on bund and forming spoil bank neatly. | C.yd | 34,512 |
| 2 | Embankment by pit earth with watering and tamping .. | " | 3,190 |
| 3 | Turfing .. ... | S.yd. | 2,188 |
| | II. *Repairing Masonry works (madaveys, etc., on channel — Over a length of six miles.* | | |
| 1 | Resetting the old revetment with new jelly ... | C.yd. | 51 |
| 2 | Do do ½ new rough stone | " | 84 |
| 3 | New rough stone work ... .. ... | " | 71 |
| 4 | Excavating bed of channel .. .. .. | " | 963 |
| 5 | Silt clearing in bed of channel ... ... ... | " | 10 |
| 6 | Earthwork embankment for training bank ... ... | " | 237 |
| 7 | Do including watering and tamping, etc. ... | " | 156 |
| 8 | Do backing over revetment .. ... ... | " | 755 |
| 9 | Turfing ... ... . | S.yd. | 166 |
| 10 | Removing ant-hills and filling them with sand ... ... | No | 62 |
| 11 | Cutting and removing small trees ... ... ... | " | 14 |
| 12 | Jungle clearing in the bed of channel and also on the top of bund, etc., complete. | Miles | 6 |

| No. | Details | Unit | Quantity |
|---|---|---|---|
| 13 | Painting grade stones with white lead and figuring with Japan | No. | 97 |
| 14 | Do mile stone ... ... | ,, | 6 |
| 15 | Providing new grade stone with painting, figuring, etc., complete. | ,, | 1 |
| 16 | Burnt size stone in mortar ... ... ... | C.ft. | 22 |
| 17 | Burnt brick in surki mortar ... ... ... | ,, | 116 |
| 18 | Burnt stone slabs ... ... ... | S.ft. | 220 |
| 19 | Plastering with surki mortar ... ... ... | Sqr. | 16·25 |
| 20 | Burnt brick in chunam ... ... ... | C.ft. | 32 |
| 21 | Pointing with surki mortar ... ... ... | Sqr. | 2·85 |
| 22 | Removing and refixing the fallen stone slabs ... ... | Sq.ft. | 292 |
| 23 | Providing teakwood shutters with wrought iron patties alround | S.ft. | 30 |
| 24 | Providing locks and keys to the shutters ... ... | No. | 17 |
| 25 | Removing the front head wall inserting the shutter and fixing wrought iron plate with eyes and reconstructing, etc., complete. | ,, | 28 |
| 26 | Repairing the leaky syphon and removing the masonry after opening the pipe and barrel and repairing by masonry material, etc., complete. | Lump | sum |
| 27 | Repairing the syphon No. 2 by removing silt from the syphon and repairs to walls and surki plastering, etc., complete. | Lump | sum |
| | III. *Constructing an aqueduct in* 7/6. | | |
| 1 | Earthwork excavation ... ... ... | C.yd. | 44 |
| 2 | Stone jelly concrete in surki mortar ... ... ... | C.ft. | 139 |
| 3 | Burnt size stone in surki mortar ... ... ... | ,, | 458 |
| 4 | Burnt brick in surki mortar ... ... ... | ,, | 153 |
| 5 | Burnt stone slabs ... ... ... | S.ft. | 244 |
| 6 | Pointing with surki mortar ... ... ... | Sqr. | 4·57 |
| 7 | Plastering with surki mortar ... ... ... | ,, | 4·33 |
| 8 | Rough stone work (new) ... ... ... | C.yd. | 34 |
| 9 | Draft clearing and unforeseen items ... ... ... | Lump | sum |

V. V. PATANKAR,
*Executive Engineer.*

## MYSORE DIVISION.

*Abstract Notification dated 4th February* 1930.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 13th February 1930, intimating the last date of tender for constructing Sericultural Farm at Mugur, T.-Narsipur Taluk.

N. G. KRISHNA IYENGAR,
*Executive Engineer.*

## MYSORE SPECIAL DIVISION.

*Abstract Notice dated 7th February* 1930.

The attention of the public is invited to the notice dated 5th February 1930, calling for tenders for constructing a General Ward in the Princess Krishnarajammanni Tuberculosis Sanatorium, Mysore at Mysore, published on pages 174 and 175 of Part VI of the *Mysore Gazette*, dated 13th February 1930.

The last date for receipt of tenders is 1st March 1930.

---

*Abstract Notice dated 1st February* 1930.

Attention of the public is invited to the notice dated 1st February 1930, calling for tenders for extending the University Offices at Mysore published in detail on page 175 and 176, Part VI of the *Mysore Gazette*, dated 13th February 1930.

The last for receipt of tenders is 8th February 1930.

*Notice Dated 8th February 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 8th March 1930, till 12 noon for Improving the Women's Hostel, Mysore. An abstract of approximate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 a.m. and 5 p.m. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred only (Rs. 100) which as earnest money and to be entered as "Tender for Improving Women's Hostel, Mysore" on the cover in which tenders will be enclosed.

5. The Chairman reserves to himself the right of rejecting the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be noted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. No tender stating "percentage less than the lowest tenderer as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concession or higher rates will be entertained.

11. The work to be executed as per D. P. W. Specification.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

*Abstract.*

| Sl. No. | Items of work | Quantity | Unit | Rate |
|---|---|---|---|---|
| | | | | Rs. |
| 1 | Flooring with 1st class Mangalore square tiles on mortar bed after raising out the old plaster and fixing in the undulation to bring it to uniform level and cement pointing complete. | 14·98 | Sqr. | |
| 2 | Flooring with 1st class Mangalore pattern square tiles on 2" concrete bed and cement pointing complete. | 17·80 | " | |
| 3 | Providing and fixing iron bars for windows ... | L. S. | lbs. | |
| 4 | Providing cement mortar concrete drain including cement plastering and covering with old slabs as per design (1½×1') | 250 | R.ft. | |
| 5 | Flooring with burnt stone slabs 3" to 4" on 3" concrete bed and cement pointing and the top and sides roughly dressed. | 4·30 | Sqr. | |
| 6 | Removing the present old pedestal of floors side plaster of walls around kitchen and latrine. | L. S. | ... | |
| 7 | Cement plastering ½" thick the interior of walls around over chunam mortar. | 7·00 | Sqr. | |
| 8 | Chunam mortar plastering ... ... | 7·00 | " | |
| 9 | Minor Improvements to Christian bath rooms as per details. | L. S. | ... | |

V. V. KARVE,
*Executive Engineer.*